city, town

Harrisburg

**United States Department of the Interior National Park Service** 

# National Register of Historic Places Inventory—Nomination Form

For NPS use only

received

date entered

Pennsylvania

state

	ns in How to Com —complete appl			ster Forms			*
1. Nam	ie						
historic	Thayer-Th	ompson	House				
and/or common	N/A						
2. Loca	ation		· ·			,	
street & number	605 West Eig	hth Str	reet			N/A not for publicat	ion
city, town	Erie		N/ <u>A</u> v	icinity of		<u></u>	
state Penn	sylvania	code	42	county	Erie	code 0	49
3. Clas	sificatio	n					
Category  district X building(s) structure site object	Ownership public X private both Public Acquisit In process being consider		Accessib	cupied in progress	Present Use agriculture commercial educational entertainment government industrial military	museum park private resi religious scientific transportati	
<b>4. O</b> wn	er of Pro	per	ty				
name Ms. I	Micheline Just	man					
street & number	605 West Eig	jhth Sti	reet				
city, town	Erie		N/A v	icinity of	state	Pennsylvania	16502
5. Loca	ation of I	Lega	l Des	criptio	on		
courthouse, regi	stry of deeds, etc.	Regist	ter of De	eds Office	e, Erie County Cou	rthouse	
street & number		140 We	est Sixth	Street			
city, town	Erie				state	Pennsylvania	
6. Repi	resentat	ion i	n Exi	sting \$	Surveys		
E litle Northwest	rie County Surv Institute of	/ey Researd	:h	has this prop	perty been determined e	ligible? yes	_X_ no
date Summer	1982				federal _x_ sta	ite county	local
depository for su	rvev records	Pennsy	lvania His	storical and	Museum Commissio	n	

#### 7. Description

Condition  X excellent deteriorated good ruins fair unexposed	Check one unaitered altered	Check one  X original site moved date	R74	
<del></del>				

#### Describe the present and original (if known) physical appearance

The Thayer-Thompson House is located at the southwest corner of West Eighth and Cherry Streets in the City of Erie, Pennsylvania. Its builder, Oscar Cornelius Thayer, created a composite of two Italian house styles: the Tuscan Villa and the Italianate. The Tuscan Villa attributes of the Thayer-Thompson House include: a heavily-bracketed and overhanging cornice, relatively flat roof, belvedere centered on the roof and smaller windows on the second floor than on the first floor. Its Italianate attributes include: an asymmetrical shape, smaller-scale, arcaded entryway and bracketed, centered roof gables. It is a two-story, common bond, brick building with a five-bay front facade, seven west side bays and five east side bays. The Thayer-Thompson House is a detached building of irregular shape and has retained its distinctive Italianate architectural features. There are two unintrusive additions to the rear of the building (see floorplan showing chronological development).

The Thayer-Thompson House has a hipped tin roof with a centered gable on all exterior walls. The roof has overhanging eaves and a cornice with modillions, dentils, and brackets at the corners. The square belvedere centered on the roof has cornice details like the rest of the house. Three round-headed windows are on each side of the belvedere, the middle window being larger and taller than the ones on either side. The first-story windows are double-hung, four-over-four with round-headed arches and are taller than the second-story windows. The second-story windows are double-hung, four-over-four with segmental arches. The entryway (vestibule) on the west side, tallest section of the building, was once open and arcaded with two Corinthian pillars and two Corinthian pilasters abutting the building. When enclosed in the 1930's, all the pillars became pilasters, and a frame double door was added with a multi-light arched The features of the second set of doors in the vestibule will be discussed at the beginning of the paragraph outlining important interior features. The cornice of the front entryway also has brackets and modillions. The shorter east section of the house has a frame front porch with spool and spindle balustrade, decorative posts with elaborate scroll-shaped brackets and dentils at the cornice. The porch also has a lattice-work base. Another three round-headed window combination identical to the one on the belvedere is repeated on a larger scale over this porch. There is an oculus window at the gable peak of the east wall.

The second set of double doors in the vestibule of the Thayer-Thompson House has raised panels and a rounded-arch transom with a painted glass design of roses. This arched double door is outlined by a carved twisted rope configuration which is repeated on other ceiling mouldings throughout the house. This twisted rope outline comes together at a lion's head "keystone" over the transom. The front hallway features an open-well stairway with two flights and balusters. There are elaborate ceiling mouldings and a circular medallion surrounds the chandelier fixtures.

The formal double parlor can be entered to the right, just inside the front door. This room is the epitomy of an elegant, Italian, formal parlor. The marble fireplaces have round-arched openings, decorative colonettes and paneled spandrels. The "keystone" on the fireplace is an acanthus leaf. The fireplaces have gilded mirrors for overmantels. The formal parlor is divided roughly in half by an elliptical arch.

#### 8. Significance

Period prehistoric 1400–1499 1500–1599 1600–1699 1700–1799 1800–1899 1900–	Areas of Significance—C  archeology-prehistoric agriculture architecture art commerce communications	heck and justify belo community planni conservation economics education engineering exploration/settled industry invention	ing landscape architectur law literature military music	religion science science sculpture social/ humanitarian theater transportation other (specify)
Specific dates	C. 1861	Builder/Architect	Oscar Cornelius Thayer	·

#### Statement of Significance (in one paragraph)

The Thayer-Thompson House, located at 605 West Eighth Street in Erie, Pennsylvania,

is a largely intact, fine example of an Italianate mansion.

It is associated with two prominent trie businessmen whose personal and professional lives converged many times between 1853 and 1887. The oil refinery which Oscar Cornelius Thayer and Victory Marion Thompson operated at different periods of their lives was, by the turn of the century, purchased by Atlantic Refinery Company (Standard Oil Company).

Completed in 1861, the Thayer-Thompson House is the epitomy of the romantic new style of picturesque architecture, the virtues of which A.J. Downing extolled in his book The Architecture of Country Houses. O.C. Thayer built this brick house on "a country lot", then on the fringes of the Borough of Erie. The design included all the details appropriate for an elaborate Italianate Mansion: an arcaded entrance, round-headed windows and doors, an overhanging cornice with brackets and modillions, and a square belvedere on the roof. As West Eighth Street developed as a primary commercial and residential thoroughfare from the 1860's to the 1880's, the style of the Thayer-Thompson House was copied by other families involved in Erie's shift from a shipping economy to an industrial one. The house on the northwest corner of Eighth and Cherry Streets, directly across from the Thayer-Thompson House, was built later and provides an example of an Italianate residence whose distinctive architectural details have been altered and therefore lost through the years.

Oscar Cornelius Thayer was born in Bennington, Vermont, on September 3, 1827, and was raised and educated there until his departure at age 21 in 1848. He sought his fortune in the lumber regions of Michigan before coming to Erie in the spring of 1853. On settling in Erie he engaged in the manufacture of what was known as stoneware, having a factory on the old canal (Erie Extension Canal, 1844 to 1871) at Third Street. During his first thirty years in Erie, O.C. Thayer also engaged in the building business. It may have been to demonstrate his building skill that O.C. Thayer built this asymmetrically-shaped Italianate residence on the very visible corner of Eighth and Cherry Streets. This was the same property which his wife, Anna Hughes, had purchased from her parents, James and Emily Hughes, for one hundred dollars in 1860. O.C. Thayer would later build a symmetrically-shaped, Tuscan Villa residence of his own on the northeast corner of Eighth and Walnut Streets. He resided at 462 West Eighth Street until his death in 1905. That home was soon after demolished.

Victory Marion Thompson was born in Madison County, New York, August 7, 1829. Victory came to Erie County with his parents, Joseph S. and Rachel Thompson in 1832, settling in a log house at the northwest corner of Liberty and Eighteenth Streets, then in Millcreek Township. Joseph Thompson died in 1837, when Victory was eight years old.

## 9. Major Bibliographical References

See Continuation Sheet

40 Coographic	al Data		<del> </del>	
10. Geographic	·			
Acreage of nominated property Quadrangle name <u>ERIE SOUTH</u> .			(	Quadrangle scale 1:24,000
UTM References				
A 11 7 5 7 4 6 0 0 4 6 C Nort	6 6 3 5 0 0 hing	B į	one Easting	Northing
c		ے م		
E	<del></del>	F		
		нГ		
Verbal boundary description as	nd justification			
See Continuation Sh	neet			
List all states and counties for	properties overla	ipping state	or county bo	ındaries
state N/A	code N/A	county	N/A	code N/A
state N/A	code N/A	county	N/A	code N/A
11. Form Prepa	red By		· · · · · · · · · · · · · · · · · · ·	
<u> </u>			<del>.</del>	
name/title Shirley R. French	, Director			
organization Preservation Proj	ject of Erie In	nc.	date May	
street & number 417 State Stre	eet		telephone	(814) 454-1813 (814) 665-3183
city or town Erie			state	Pennsylvania 16501
•	ric Prese	rvatio		er Certification
The evaluated significance of this p				
national	•	_X local		
As the designated State Historic Pre 665), I hereby nominate this propert according to the criteria and proced	y for inclusion in the jures set forth by the	e National Reg	gister and certify	
State Historic Preservation Officer s	ignature			
title Dr. Larry E.Tise, State	Historic Preserv	ation Offic	er	date
For NPS use only I hereby certify that this prope	rty is included in the	National Rec	iister	
i nereby certify that this prope	rty is included in the	, radonai neţ	ji <del>otoi</del>	date
Keeper of the National Register		<del></del>		ugic
Attest:				date
Chief of Registration		<del></del>	<del></del>	

#### United States Department of the Interior National Park Service

## National Register of Historic Places Inventory—Nomination Form

Thayer-Thompson House


Continuation sheet

Item number

7

Page

?



The master bedroom was located directly above the parlor when V.M. Thompson resided here. It now houses one apartment but the fireplace and ceiling mouldings remain intact and in very good condition. There are two staircases to the rear of the building. The first is a one-run, single-flight stairway which is accessible from the southeast corner entryway. The other staircase has been boarded up, and is a dog-leg stair with winder. This latter stair provided access from the kitchen to the second-floor, servant's quarters.

## United States Department of the Interior National Park Service

## National Register of Historic Places Inventory—Nomination Form

Thayer-Thompson House, Erie County Continuation sheet

Item number

8

Pąge

2

These circumstances demanded that Victory work at an early age to help support the family. He began peddling Yankee notions and later manufactured washboards while attending the old Erie Academy. In 1848, when nineteen years of age, Victory sold his washboard business and bought a canal boat which he sailed along the Erie Extension Canal for three years. He then attended Meadville College for one year, working his way by buying and selling coal in Meadville. He also started the "Thompson Line", which by 1855 consisted of sixteen canal boats. During this period he was also operating a coal yard on West Eighth Street.

The July 30, 1863, issue of the Erie Weekly Gazette reports a new enterprise for V.M. Thompson. "Our City and County is liberally represented in the busy throng seeking for wealth in the Titusville portion of the oil region...Prominent among the lucky ones at the wells is V.M. Thompson, who has already acquired a handsome fortune." At this time V.M. Thompson and wife Rebecca set out to find a home befitting a now wealthy oil dealer and purchased from Oscar Cornelius Thayer the Italianate residence at the southwest corner of Eighth and Cherry Streets on September 9, 1863. In 1864 V.M. Thompson formed the Thompson Oil Company and by this time was able to contract the services of Stewarts of New York City to design and decorate their formal front parlor. V.M. Thompson later owned and operated the Erie City Oil Works, one of the early refineries in the United States. He resided in the house until 1886 and died in Cleveland, Ohio, October 22, 1887. O.C. Thayer then purchased the refinery, which he in turn sold to the Atlantic Refinery Company (Standard Oil Company).

The Thayer-Thompson House was called "one of the best-preserved early Victorian buildings in the city" in the recently published Historic Erie Design Guide (Weber, 1983). The overhanging cornice, brackets, modillions, belvedere and arcaded entrance remain intact and in very good condition. A frame, one-story, one-car, garage was added at the southwest corner of the house circa 1925. The free-standing, arcaded entrance was enclosed about 1935, creating Corinthian pilasters where free-standing columns once stood. Ownership of the house left the Thompson family in 1940 and new owners, John and Rose Banka had converted the one-family residence into five apartments by 1945. To facilitate this conversion a first-story master bedroom was added abutting the north wall of the garage and west wall of the house. Three chimneys were also removed. Because these additions were made to the rear of the house, the Thayer-Thompson House still creates a Victorian oasis on the southwest corner of Eighth and Cherry Streets. Since 1972 Micheline Justman has owned the Thayer-Thompson House and has worked to retain its original beauty.

### United States Department of the Interior National Park Service

# National Register of Historic Places Inventory—Nomination Form

es

For MPG (see only security of the security of

Thayer-Thompson House Continuation sheet

Item number

g

Page

1

Major Bibliographical References

Conley, Katharine. "The Italian Style." <u>The Old-House Journal</u>, vol. IX. no. 1, January 1981, pp.1 & 14-19.

Conley, Katharine. "Italian Style Decoration." The Old House Journal, vol. IX. no. 2, February 1981, pp. 33-36.

Downing, A.J. The Architecture of Country Houses. (New York: Dover Publications Inc., 1969)

Erie City Directories. 1853 - Present.

Erie County Recorder of Deeds Office. Deed Book no. 54, p. 151.

Erie Weekly Gazette, p.2, col. 5. July 30, 1863.

History of Erie County, Pennsylvania. 1884, p. 962.

Justman, Micheline. "Thayer-Thompson House." (A narrative history available at the Preservation Project of Erie Inc. office)

Lewis, Harry W. "Early History of Erie County and Vicinity." <u>Erie Daily Times</u>, September 9, 1911.

Miller, John. Twentieth Century History of Erie County, Pennsylvania. 1909. vol. II, pp. 129 & 219-221.

Reed, John Elmer. History of Erie County, Pennsylvania. 1925. vol.I, pp. 512 & 513.

Weber, Tom. <u>Historic Erie Design Guide</u>. (Erie: Preservation Project of Erie Inc., 1983) p.8.

Wright, Alice Thompson. Former resident of the Thayer-Thompson House - Interviewed April 24, 1985.


### **United States Department of the Interior**National Park Service

# National Register of Historic Places Inventory—Nomination Form

Thayer-Thompson House Continuation sheet

Item number

10



Page

Verbal Boundary Description

From Erie County Deed Book No. 1368, Pg. 28:

Beginning at a point at the intersection of the south line of 8th Street and the westerly line of Cherry Street; thence south 64° 02' West along the southerly line of 8th Street, 100 feet to a point; thence south 26° east on a line parallel to the westerly line of Cherry Street, 108.82 feet to a point; thence north 64° 02' East, 33 feet to a point; thence north 33° 02' east, 21 feet to a point; thence north 64° 02' east, 49 feet to a point on the westerly line of Cherry Street; thence north 26° west along the westerly line of Cherry Street, 98 feet to the place of beginning.